



NOTES:

1. INSTALL PERMANENT BINDER COURSE, CURBING AND BACKFILL BEHIND CURBING BY NOVEMBER 15TH EACH YEAR BEFORE WINTER. ALL UTILITY WORK ON THOSE IMPACTED STREETS SHALL BE COMPLETED PRIOR TO INSTALLING BINDER COURSE. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING ALL NEW TEMPORARY AND PERMANENT PAVEMENT THROUGHOUT THE DURATION OF THE PROJECT.
2. PROVIDE ADDITIONAL GRAVEL IF REQUIRED. REMOVE AND DISPOSE OF EXCESS GRAVEL.
3. APPLY TACK COAT AT ALL TRANSITIONS BETWEEN NEW AND EXISTING PAVEMENT SEAL WITH HOT POURED RUBBERIZED ASPHALT.



**DEPARTMENT OF PUBLIC WORKS
ENGINEERING DIVISION
TOWN OF BILLERICA,
MASSACHUSETTS**

**ROAD RECLAMATION
PAVEMENT**

CREATED BY: DCW/KCS

SCALE: NTS

FILE:

CHECKED BY: GA/JT

DATE: 06/29/2015